



St Andrews Carendale Brisbane City Council



Applicator:
Brisbane CityWorks

Engineer:
Brisbane City Council

Project Size:
500m²

Crew Size:
Three (3)

Templates Used:
Diagonal
Herringbone
Stacked Brick

Coatings Used:
SP50
Sanford Tan
Black Speckle

Other Equipment Used:
Infrared
Hopper Gun
Hand Pressure
Sprayer

Brisbane City Council came under pressure from the local residents in St Andrews Estate Carendale regarding the hazards and appearance of the hand laid bricks.

Various paving options were considered and presented to the local residents with **StreetPrint** being chosen for its ability to satisfy all criteria from shifting to aesthetics as requested by the residents.

1500m² of Paving Stones were removed and due to budget restraints 500m² of StreetPrint was applied consisting of Herringbone threshold treatments and a Brick Border banding in a Tan Colour with Black speckles throughout to match the existing pavers in other stages of the subdivision.

Three men completed the project in four days both in conjunction with laying of the asphalt and reheating the existing asphalt.

StreetBond SP50 was applied providing the colour and aesthetic look required for the residents of St Andrews.